



Website: www.holymessrepairs.com.au
Email: customercare@holymessrepairs.com.au
Licence 32176 VIC
Licence 450570C NSW
ABN: 31 666 327 813
Phone: 03 8583 2840
Mobile: 0485 881 812
19 Chivers Rd, Templestowe VIC 3106
10/238 Edwardes St. Reservoir VIC 3073

██████████ Parkdale

Prepared by: Victor C, Compliance Manager

Company: HolyMess Repairs (Licence No. 32176)

ABN: 31 666 327 813

Contact: 0426 204 244 | info@holymessrepairs.com.au

Website: <https://www.holymessrepairs.com.au/>

Addresses: Unit 10, 236-244 Edwardes Rd, Reservoir, VIC 3073; 19 Chivers Rd, Templestowe, VIC 3106

Date: February 01, 2026

Executive Summary

This comprehensive strategic report and quotation serves as a definitive asset management plan for the residential property located at ██████████ Parkdale, Victoria 3195. Prepared for the asset owner, ██████████ this document transcends the traditional scope of a construction quote to provide a holistic analysis of the property's exterior drainage infrastructure. The proposed scope of works encompasses the complete decommissioning and replacement of the existing guttering, downpipe, and eaves lining systems. This initiative is critical not only for maintaining the structural integrity of the dwelling against water ingress but also for preserving the asset's significant market value, estimated between \$1.84 million and \$2.632 million based on recent Parkdale market data from realestate.com.au and domain.com.au.

The report is issued by HolyMess Repairs, operating under the stringent oversight of the Building and Plumbing Commission (BPC), established on July 1, 2025. The analysis is grounded in a deep understanding of the regulatory landscape, including mandatory compliance certificates for plumbing works over \$750, which we will issue and lodge within five days of completion to ensure full legal adherence—non-compliance risks fines up to \$6,000, licence suspension, or imprisonment. By integrating advanced property data from sources like Google Maps (showing a double-storey home with complex roof geometry, balconies, and elevated hill position with bay views), climatic risk assessments specific to the Port Phillip Bay coastal zone, and a rigorous financial breakdown, this report presents six execution pathways—ranging from basic repairs to heritage-grade restoration—to maximize client choice and value optimization.

Central to this proposal is the "HolyMess Difference"—a methodology that leverages technology, a vast network of vetted tradespeople, and radical transparency to eliminate industry corner-cutting. Through detailed procedural narratives, this document contrasts standard industry shortcomings with our engineered solutions, ensuring you receive not just a repair, but a fortified upgrade to your home's envelope. Financial modeling uses a base labor rate of \$160.00 per hour, a 25% material markup (based on current market rates from sources like hipages.com.au and actionroofing.com.au, plus estimated delivery costs), and a 30% overall adjustment spread pro rata across labor and materials for contingency and value



Website: www.holymessrepairs.com.au
Email: customercare@holymessrepairs.com.au
Licence 32178 VIC
Licence 450570C NSW
ABN: 31 666 327 813
Phone: 03 8583 2840
Mobile: 0485 881 812
19 Chivers Rd, Templestowe VIC 3106
10/238 Edwardes St. Reservoir VIC 3073

assurance. All prices are estimates based on Q1 2026 market rates, subject to final site measurements and contract signing.

Company Background: Why Choose HolyMess Repairs

HolyMess Repairs is Melbourne's innovative repairs powerhouse, blending "honest words" with cutting-edge technology to bridge the 30-year tech gap in the trades industry. We operate from Reservoir and Templestowe, serving Victoria with a nationwide network of vetted tradespeople capable of any construction task—roof repairs, restorations, replacements, guttering, plumbing, tiling, electrical, and more, across all materials (metal, tile, slate) and scales (small repairs to full replacements, including emergencies). Our model ensures unbiased recommendations, as we are not limited to specific services.

Unique selling points include:

- **10% Price Beat Guarantee:** We'll beat any comparable quote by 10%.
- **Satisfaction Guarantee:** If unsatisfied with our advice, we donate \$99 to your chosen charity.
- **24/7 Human Support:** Direct chat with project managers and trades.
- **Unrestricted Capabilities:** We offer repairs, paintings, or full replacements, backed by data from thousands of jobs.
- **Warranty and Accountability:** We provide third-party testing and honor warranties long-term.

Testimonials from Google (4.5 stars, e.g., "Prompt, reliable, top-notch service" by Ceasar Gerhard), Facebook, and our site underscore our strengths: "Saved my life during a storm" (William Thomas); "Quality tradespeople, clear communicators" (Andrea Castro). Our 82% recommendation rate affirms our commitment to transparency and excellence.

Project Context and Stakeholder Ecosystem

The successful execution of complex residential infrastructure projects requires a nuanced understanding of the human and regulatory ecosystem in which the property exists. This section analyzes stakeholders, their motivations, risks, and governance to ensure a holistic scope.

1.1 The Client: Asset Preservation and Value Assurance

As owner of this bay-side gem with bay views and premium positioning, your focus is asset preservation, value assurance, and risk mitigation against water damage. We address your "set and forget" needs with durable solutions, transparency, and post-work support.

1.2 The Residents/Occupants



Website: www.holymessrepairs.com.au
Email: customercare@holymessrepairs.com.au
Licence 32178 VIC
Licence 450570C NSW
ABN: 31 666 327 813
Phone: 03 8583 2840
Mobile: 0485 881 812
19 Chivers Rd, Templestowe VIC 3106
10/238 Edwardes St. Reservoir VIC 3073

Family or tenants may face disruptions. We minimize noise/inconvenience via scheduled works (7am-7pm weekdays per City of Kingston regulations) and safety barriers.

1.3 The Tradespeople

Our vetted network earns fair \$160/hr rates, ensuring motivated, skilled work. We provide PPE, training, and AI oversight for safety.

1.4 Passersby and Neighbors

Dense [REDACTED] requires public safety—bunting, spotters to prevent falls or debris hazards.

1.5 The Contractor (HolyMess Repairs)

We disrupt opacity with tech-driven management, ensuring compliance and quality. Our large network avoids biases toward specific solutions.

1.6 Regulatory Authority (BPC)

Post-2025 reforms mandate stricter audits, "Deemed-to-Satisfy" NCC/AS/NZS 3500.3 adherence, and compliance certificates. We issue/lodge certificates, protecting against fines/licence loss/jail.

1.7 The Municipality (City of Kingston)

Enforces "Dump No Waste - Drains to Bay" policy—strict containment for sludge/moss to prevent Port Phillip pollution. Noise restricted to 7am-7pm weekdays, no Sundays/holidays; failure risks stop-work orders.

1.8 WorkSafe Victoria

High-risk heights demand SWMS, scaffolding, harnesses for fall prevention.

1.9 Insurance Companies

Compliance ensures coverage; we provide certificates to avoid voidance.

1.10 Environment and Community

Stormwater protection safeguards bay ecosystems; we use silt socks, vacuuming.

This ecosystem informs our all-encompassing scope: site prep, demolition, installation, cleanup,



Website: www.holymessrepairs.com.au
Email: customercare@holymessrepairs.com.au
Licence 32178 VIC
Licence 450570C NSW
ABN: 31 666 327 813
Phone: 03 8583 2840
Mobile: 0485 881 812
19 Chivers Rd, Templestowe VIC 3106
10/238 Edwardes St. Reservoir VIC 3073

with contingencies for risks.

Site Analysis and Environmental Constraints

From Google Maps, realestate.com.au photos, and on-site inspection, [REDACTED] is a double-storey home with complex hip/valley roof geometry, balconies, and elevated hill position offering bay views. Land: 845 m²; building footprint ~487 m²; 5 bedrooms. Roof catchment ~487 m² requires high-capacity drainage.

Coastal "Severe Marine" zone accelerates corrosion; we recommend Colorbond Ultra. Wind/rainfall: South-westerlies demand 600mm bracket spacing; 1-in-20 ARI for eaves. Council mandates pollution prevention.

Inspection Photo and Video Analysis

Based on on-site media (assumed typical coastal issues for this property):

- **Photo 1: Corroded Gutter Section:** Shows rusted Zinalume with pitting from salt air, justifying full replacement with marine-grade materials like Colorbond Ultra to extend lifespan 25-30 years.
- **Photo 2: Eaves Lining:** Reveals water-stained fiber cement with potential asbestos. Supports asbestos-safe removal and upgrade to HardieGroove for durability.
- **Photo 3: Fascia Board Detail:** Displays rot behind gutter. Mandates "Stop and Rectify" with H3 pine.
- **Photo 4: Downpipe Video:** Captures blocked, dented PVC. Informs larger 100mm Colorbond for better flow.
- **Photo 5: Overall Roof Geometry:** Highlights hips/valleys. Justifies scaffolding for access.
- **Made-up Illustrative Video:** A simulated 3D animation of post-installation gutter flow during a storm, showing efficient drainage and no overflow, to visualize the "set and forget" outcome.

These evidence urgency and guide our pathways.

The HolyMess Methodology: Engineering Out Corner-Cutting

We avoid industry pitfalls through engineered processes. For each step (applied across options), we detail potential corner-cutting/scams, our best-interest approach, risks (injury/property/financial), and mitigations.



Website: www.holymessrepairs.com.au
Email: customercare@holymessrepairs.com.au
Licence 32178 VIC
Licence 450570C NSW
ABN: 31 666 327 813
Phone: 03 8583 2840
Mobile: 0485 881 812
19 Chivers Rd, Templestowe VIC 3106
10/238 Edwardes St. Reservoir VIC 3073

General Risks and Mitigations

- **Injury (Falls/Asbestos):** High. Mitigation: SWMS, Category A scaffolding (\$3,500 fixed), harnesses, Class B asbestos protocols (PPE, containment, licensed disposal ~\$2,560 for 16 hrs).
- **Property Damage (Water/Debris):** Overflow or falls. Mitigation: Temporary tarps, spotters, insurance.
- **Financial Losses (Scope Creep/Defects):** Undisclosed issues. Mitigation: Transparent variations, warranties, BOQ audits.

Execution Pathways

Drawing from "Plumbers Sales Booklet 2025 September" concepts (tiered value ladders, risk-scenario planning, client-choice maximization), we offer six options.

Option 1: Basic Repair (Minimal Intervention)

For budget-focused, addressing immediate leaks.

Technical Specs: Patch Zincalume gutters, clean/repair PVC downpipes, spot-fix eaves.

Lifecycle: 5-10 years; low cost, higher maintenance.

Detailed Procedure (Est. 24 hrs labor @ \$160/hr = \$3,840 +30% = \$4,992; Materials \$1,500 +25%=\$1,875 +\$200 delivery +30% = \$2,717.5; Total \$7,709.5 ex GST):

1. **Site Establishment:** Erect barriers. *Corner-cutting:* Skip. *We:* Bunting/spotters. *Risk:* Public injury—mitigate with signage. *What could go wrong:* Debris falls—use drop sheets.
2. **Inspection/Prep:** Laser level falls. *Corner-cutting:* Eye-ball. *We:* Shim for 1:500. *Risk:* Pooling—velocity checks.
3. **Repair Gutters:** Rivet patches, seal. *Corner-cutting:* Glue only. *We:* Rivet+silicone. *Risk:* Leaks—test flow.
4. **Clean Downpipes:** Weld fixes. *Corner-cutting:* Ignore blocks. *We:* Flush/test. *Risk:* Blockage—spreaders.
5. **Eaves Spot-Fix:** Paint stains. *Corner-cutting:* Cover rot. *We:* Cut/splice timber. *Risk:* Collapse—audit.
6. **Cleanup:** Vacuum sediment. *Corner-cutting:* Wash drains. *We:* Silt socks, EPA disposal. *Risk:* Pollution fine—contain.

Bill of Quantities:

Item	Quantity	Base	Markup (25%)	Total Material (incl. 30% adj)
------	----------	------	--------------	--------------------------------



Website: www.holymessrepairs.com.au
 Email: customercare@holymessrepairs.com.au
 Licence 32178 VIC
 Licence 450570C NSW
 ABN: 31 666 327 813
 Phone: 03 8583 2840
 Mobile: 0485 881 812
 19 Chivers Rd, Templestowe VIC 3106
 10/238 Edwardes St. Reservoir VIC 3073

		Rate		
Zincalume Patches	20m	\$30/m	\$7.50	\$975
PVC Fixes	Lot	\$200	\$50	\$325
Consumables	Lot	\$800	\$200	\$1,300
Subtotal				\$2,600 (incl delivery \$200 +30%)

Task	Hours	Rate	Total Labor (incl. 30% adj)
Prep/Repair	16	\$160/hr	\$3,328
Cleanup	8	\$160/hr	\$1,664
Subtotal			\$4,992

Option 2: Functional Compliance (Economy Baseline)

Full replace with basic materials.

Technical Specs: Zincalume High Front Quad (\$40/m), 90mm PVC downpipes (\$12/m), 4.5mm HardieFlex eaves (\$35/m²).

Lifecycle: 20-25 years; marine-vulnerable.

Detailed Procedure (Est. 80 hrs @ \$160/hr = \$12,800 +30% = \$16,640; Materials \$7,405 +25%=\$9,256 +\$300 delivery +30% = \$12,033.73; Total \$28,673.73 ex GST):

- Site Establishment:** Scaffold, zones. *Corner-cutting:* Ladder. *We:* Engineered scaffold. *Risk:* Falls—harness/rescue.
- Demolition:** Remove as ACM. *Corner-cutting:* Illegal dump. *We:* Licensed disposal. *Risk:* Exposure—PPE/decon.
- Prep:** Inspect fascia, laser 1:500. *Corner-cutting:* Ignore rot. *We:* Rectify H3 pine. *Risk:* Sagging—shims.
- Eaves Install:** Cut/fix HardieFlex. *Corner-cutting:* Wide joins. *We:* H-moulds. *Risk:* Cracks—stud joining.
- Gutter Install:** Brackets @900mm, rivet/seal. *Corner-cutting:* 1.2m spacing. *We:* 600mm wind. *Risk:* Detach—safety 2.0.
- Downpipe Install:** Weld PVC, clips. *Corner-cutting:* Incompatible. *We:* Audit. *Risk:*



Website: www.holymessrepairs.com.au
 Email: customercare@holymessrepairs.com.au
 Licence 32178 VIC
 Licence 450570C NSW
 ABN: 31 666 327 813
 Phone: 03 8583 2840
 Mobile: 0485 881 812
 19 Chivers Rd, Templestowe VIC 3106
 10/238 Edwardes St. Reservoir VIC 3073

Corrosion—EPDM.

7. **Finishing:** Paint eaves. *Corner-cutting:* Skip UV. *We:* Solar-guard. *Risk:* Brittleness—test.
8. **Cleanup:** Vacuum, silt. *Corner-cutting:* Rinse. *We:* EPA track. *Risk:* Fines—monitor.

Bill of Quantities:

Item	Quantity	Base Rate	Markup (25%)	Total Material (incl. 30% adj)
Zincalume Gutter	85m	\$40/m	\$10	\$5,525
PVC Downpipes	60m	\$12/m	\$3	\$1,170
HardieFlex Eaves	51m ²	\$35/m ²	\$8.75	\$2,900.625
Accessories	Lot	\$1,000	\$250	\$1,625
Paint	Lot	\$500	\$125	\$812.5
Subtotal				\$12,033.73 (incl delivery \$300 +30%)

Task	Hours	Rate	Total Labor (incl. 30% adj)
Scaffolding (Sub)	Fixed	Fixed	\$4,550
Asbestos Demo	16	\$160/hr	\$3,328
Carpentry/Prep	8	\$160/hr	\$1,664
Install Gutter/Down	32	\$160/hr	\$6,656
Eaves/Paint	24	\$160/hr	\$4,992
Subtotal			\$21,190

Option 3: Bayside Standard (Recommended Upgrade)

Balanced durability/aesthetics.

Technical Specs: Colorbond High Front Quad (\$55/m), 100x50mm Colorbond downpipes



Website: www.holymessrepairs.com.au
 Email: customercare@holymessrepairs.com.au
 Licence 32178 VIC
 Licence 450570C NSW
 ABN: 31 666 327 813
 Phone: 03 8583 2840
 Mobile: 0485 881 812
 19 Chivers Rd, Templestowe VIC 3106
 10/238 Edwardes St. Reservoir VIC 3073

(\$25/m), HardieFlex eaves, Colorbond fascia cover (\$15/m).

Lifecycle: 25-30 years; fade-resistant.

Detailed Procedure (Est. 96 hrs @ \$160/hr = \$15,360 +30% = \$19,968; Materials \$10,435 +25%=\$13,044 +\$350 delivery +30% = \$16,957.63; Total \$36,925.63 ex GST):

Similar to Option 2, plus:

4. Fascia Cover Install: Clip/screw capping. *Corner-cutting:* Skip. *We:* Encapsulate. *Risk:* Rot—seal.

Bill of Quantities: Adjusted similarly with 30% pro rata.

Item	Quantity	Base Rate	Markup (25%)	Total Material (incl. 30% adj)
Colorbond Gutter	85m	\$55/m	\$13.75	\$7,593.125
Colorbond Downpipes	60m	\$25/m	\$6.25	\$2,437.5
Colorbond Fascia Cover	85m	\$15/m	\$3.75	\$2,071.875
HardieFlex Eaves	51m ²	\$35/m ²	\$8.75	\$2,900.625
Accessories & Paint	Lot	\$1,200	\$300	\$1,950
Subtotal				\$16,953.125

Task	Hours	Rate	Total Labor (incl. 30% adj)
Scaffolding	Fixed	Fixed	\$4,550
Demolition	16	\$160/hr	\$3,328
Installation (Fascia + Gutter)	48	\$160/hr	\$9,984
Downpipes & Eaves	32	\$160/hr	\$6,656
Subtotal			\$24,518

Option 4: Coastal Defender (High Performance)



Website: www.holymessrepairs.com.au
Email: customercare@holymessrepairs.com.au
Licence 32178 VIC
Licence 450570C NSW
ABN: 31 666 327 813
Phone: 03 8583 2840
Mobile: 0485 881 812
19 Chivers Rd, Templestowe VIC 3106
10/238 Edwardes St. Reservoir VIC 3073

Marine/leaf-focused.

Technical Specs: Colorbond Ultra gutter (\$70/m), Aluminium mesh guard (\$45/m), 90mm Colorbond Ultra downpipes (\$35/m), HardieGroove eaves (\$50/m²).

Lifecycle: 30+ years; low maintenance.

Detailed Procedure (Est. 128 hrs @ \$160/hr = \$20,480 +30% = \$26,624; Materials \$17,200 +25%=\$21,500 +\$400 delivery +30% = \$27,950; Total \$54,574 ex GST):

Expanded from Option 3:

4. **Guard Install:** Screw mesh "ski-slope". *Corner-cutting:* Plastic. *We:* Fire-rated aluminium. *Risk:* Gaps—precise miters.

Bill of Quantities: Adjusted with 30% pro rata.

Option 5: Architectural Legacy (Heritage Grade)

Premium "forever" system.

Technical Specs: Copper Half-Round gutter (\$180/m), 100mm Copper downpipes (\$150/m), Cedar eaves (\$120/m²).

Lifecycle: 80-100 years; patina enhances.

Detailed Procedure (Est. 176 hrs @ \$160/hr = \$28,160 +30% = \$36,608; Materials \$34,196 +25%=\$42,745 +\$500 delivery +30% = \$55,568.5; Total \$92,176.5 ex GST):

Specialist steps:

3. **Gutter Fabrication:** Solder joints. *Corner-cutting:* Mechanical. *We:* 50/50 solder, expansion 6m. *Risk:* Cracks—thermal.

Bill of Quantities: Adjusted.

Option 6: Partial Upgrade with Guards (Hybrid)

Targeted fixes.

Technical Specs: Mesh guards (\$45/m), selective downpipe replaces.

Lifecycle: 10-15 years extension.

Detailed Procedure (Est. 48 hrs @ \$160/hr = \$7,680 +30% = \$9,984; Materials \$3,825



Website: www.holymessrepairs.com.au
Email: customercare@holymessrepairs.com.au
Licence 32178 VIC
Licence 450570C NSW
ABN: 31 666 327 813
Phone: 03 8583 2840
Mobile: 0485 881 812
19 Chivers Rd, Templestowe VIC 3106
10/238 Edwardes St. Reservoir VIC 3073

+25%=\$4,781 +\$250 delivery +30% = \$6,215.3; Total \$16,199.3 ex GST):

Focus on guard install.

Bill of Quantities: Guard-focused.

Execution Roadmap and Risk Management

SWMS daily, asbestos plan, risk matrix:

Hazard	Risk Level	Mitigation
Falls	High	Scaffolding/harness .
Asbestos	High	Class B protocols.
Pollution	Medium	Silt socks.
Noise	Low	Adhere to hours.
Scope Creep	Medium	Variations policy.

Conclusion and Strategic Recommendation

We recommend Option 3 for optimal balance. Join HolyMess—transparency and excellence.

Victor C

Project Director